Persons who have already submitted their tenders for the supply of Straw, Sundry articles and for the purchase of "Done" Calves from the Institute in response to the Gazette Notification dated 16th May 1940, may also submit re-tenders without further deposit of respective Earnest Money along with the original receipt for Earnest Money granted to them by this Office. Their previous tenders will then be considered as cancelled and replaced by such re-tenders as may be given by them.

M. RAMACHANDRA RAO,
Superintendent.

GOVERNMENT OF MYSORE—ELECTRICAL DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER BANGALORE.

Abstract Notification No. G. N. 43, dated 8th June 1940.

MATERIALS REQUIRED FOR AUTOMATIC TELEPHONE WORKS.

Attention is drawn to this office Notification dated 8th June 1940, No. G. N. 43, inviting tenders for the above work, published in Part VI, page 1429 of the *Mysore Gazette*, dated 13th June 1940. The last date of receiving tenders is 29th June 1940, 2 P.M.

Abstract Notification No. G. N. 44, dated 8th June 1940.

Attention is drawn to this office Notification, No. 44 inviting tenders for the supply of Steel cored alluminium cable No. 8 S.W.G. or No. 6 B. & S. copper, published in Part VI, pages 1429-1430 of the *Mysore Gazette*, dated 13th June 1940. The last date of receiving tenders is 1st July 1940, 12 noon.

Abstract Notification No. G. N. 45, dated 10th June 1940.

SALE OF JUNGLEWOOD SLEEPERS.

Attention is drawn to this office notification, dated ..... inviting tenders for the Sale of Junglewood Sleepers available in the Department, published in Part VI, page 1430 of the *Mysore Gazette*, dated 13th June 1940. The last date of receiving tenders is 3rd July 1940 at 12 NOON and the earnest money required is Rs. 25.

M. HAYATH,
For *Chief Electrical Engineer.*

OFFICE OF THE SUPERINTENDENT, BANGALORE POWER AND LIGHTING, BANGALORE.

Notice dated 19th June 1940.

1. Sealed tenders in triplicate will be received at the Office of the Superintendent, Bangalore Power and Lighting, Bangalore, and the same should be superscribed with the name of the work given below.
2. The plans, detailed estimates and conditions may be obtained at the Office of the undersigned at all working hours.
3. The tenders should be in the form of a statement as given below showing rates, in figures and in words, at which the different items specified will be executed.
4. The tenders may be rejected or accepted in full or in part without any reasons being assigned therefor.
5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Superintendent, Power and Lighting, Bangalore. No enquiries regarding the acceptance or rejection of a tender will receive any reply. The earnest money of rejected tenders will be returned.
6. Within 3 days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, failing which his tender will be considered cancelled and the earnest money will be forfeited.
7. The materials to be used should be of the best make and conform to the requirements of the Departmental rules and B.E.S.A. and A.I.E.E. specifications. Samples should be sent with tenders. When the samples are sent, mention should be made of manufacturers' or makers' catalogue.
8. *Name of work.*—Providing electric lights to the newly extended wings of Mysore State Life Insurance Office, Bangalore.
9. *Last date and time of receiving tender.*—3-30 P.M., 5th July 1940.
10. *Time and date of opening of tenders in public.*—4-30 P.M., 5th July 1940.
11. *Earnest money required with tender.*—Rs. 30 and Rs. 30 after acceptance of the tender.
12. *Time for completing the work from date of accepting the tender.*—Two weeks.
13. *Details of the work to be executed.*—As per specification enclosed.

N.B.—Slight alterations, if any, will have to be carried out without any extra cost.

Tender for providing electric lights to the newly built wings to the Mysore Insurance Office Building, Bangalore.

No.	Particulars	Unit	Quantity
1	Supplying and wiring in two-way T. W. casing and capping 2″×1″ using No. 14 B. & S., V. I. R. wire for 600 volts, 2,500 M. G. for lighting outlets taking tap from the existing lighting circuit for lighting outlets in the ground floor and 1st floor	No.	20
2	Do for controlling switches with 5 amps. brown bakelite reinforced tumbler switches in the ground and first floor	,,	20
3	Do for wall plugs with 5 amps. brown bakelite reinforced wall plugs with switch combined	,,	6
4	Supplying and wiring by using No. 14 B. & S. twin core lead covered wire for 600 volts with E. C. for lighting oultets in the II floor taking tap from the existing circuit	,,	10
5	Do for controlling switches with 5 amps. brown bakelite tumbler switch	,,	10
6	Do for wall plugs with 5 amps. wall plugs switch combined pattern, in II floor	,,	3
7	Supplying and fixing :—		
	(*a*) $\frac{5}{8}$″×5′ rigid pendent with heavy pattern brass back plate and $\frac{5}{8}$″ B. C. lampholder complete	,,	18
	(*b*) $\frac{5}{8}$″×1′ do do do	,,	12
	(*c*) 12″ Industrial dispersive reflectors	,,	18
	(*d*) 10″×4$\frac{1}{2}$″ white opal spherical dome with gallery complete ..	,,	12
	(*e*) Lamp M.F.B.C. 230 volts, 60 watts, pearl	,,	30
8	Masonry patching and colour washing	L. S.	..

T. H. KAIVAR,
Superintendent.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, KOLAR GOLD FIELDS.

TENDER NOTIFICATION FOR CARTING FOR THE YEAR 1940-41.

Attention is drawn to this office notification dated 10th June 1940, inviting tenders for the above work, published in Part VI, pages 1453-1454 of the *Mysore Gazette*, dated the 13th June 1940. The last date of receiving tenders is 3rd July 1940 and the earnest money required is Rs. 25.

R. PRASAD,
Superintendent.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, MYSORE.

Abstract Notification dated 10th June 1940.

The attention of the public is invited to the detailed notification dated 10th June 1940, for the carting of materials and supply of building materials in Mysore Power and Lighting and Sub-sections attached to it, published on pages 1455-1456, Part VI of the *Mysore Gazette*, dated 13th June 1940.

Notification dated 19th June 1940.

1. Sealed tenders in triplicate will be received at the Office of the Superintendent, Power and Lighting, Mysore, superscribed with the name of the work noted below.

2. A sum of Rs. 40 (Rupees forty only) is required to be sent along with the tender in cash or currency or cheque drawn in favour of the Superintendent, Power and Lighting, Mysore or Order being the earnest deposit. Tenders not accompanied with the said deposit will not be accepted.

3. The plans connected with the work may be seen at the office of the undersigned at all working hours. The same will be made available on payment of Rs. 2 per set, if required.

4. The tenders should be drawn up strictly in conformity to the specification furnished, writing out the rate at which, each item of work will be executed in figures as well as in words failing which no cognizance will be taken of the tender. No items other than those noted in the statement should be included, as the items cover provision for all sundries that are necessary for the execution of the work to meet with the requirements of the Department, including painting and colour washing to suit the finish of the walls, etc.

5. Materials to be used on the work should be of best quality conforming to the specifications of this Department and B. S. or A. I. E. E. specifications. Mention should also be made of the manufacture and the Catalogue numbers of the materials offered. Teakwood planks to be used on the work should be free from knots, cracks and should be well seasoned. No planks less than 12″ in width will be permitted to be used unless it is to make up the difference in size of the board required. Only lap joints should be adopted in all cases.

6. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

7. The successful tenderer will be required to execute an agreement within two days from the date of communication of acceptance of the tender. He should send samples of all the materials required for the work mounted on a board and start the work after obtaining the approval of the undersigned with regard to the same within a week from the date of communication of acceptance. Failure to adhere to the conditions above will entail forfeiture of the earnest deposit and adoption of such measures as are necessary for expediting the work otherwise entirely at his risk. He should also bind himself to execute the work strictly adhering to the wiring rules of this Department as well as those of I.E.E. He should also be prepared to adopt changes in the location of lighting and heating outlets control points, etc., that might be desired by the undersigned during the progress of work without any obligation if the tender is not materially affected thereby. The wiring adopted being a lead covered cable sharp corners should invariably be avoided.

8. The undersigned reserves the right to reject the work either in full or in part if the same is not executed according to the above specifications or is not satisfactory as regards workmanship.

9. Special care should be taken to afford metallic continuity and to provide efficient earthing to the installation as the system of wiring adopted is in lead covered cables.

10. *Name of work.*—Installing Electric lights and heating circuits to the Maternity Hospital Buildings at Krishnarajanagar.

11. *Last date and time for receiving the tender.*—At 3 P.M., on 2nd July 1940.

12. *Last date and time for opening the tender in public.*—At 4 P.M., on 2nd July 1940.

13. A period of four weeks from the date of acceptance of tender will be allowed for the completion of the work in all respects. If the installation is not handed over to the Department with service on the due date, the Department will have the option to take charge of the installation at whatever stage it might be and arrange for completion of the work through any other agency at the risk of the tenderer or impose a penalty of Rs. 10 (Rupees Ten) only per each week of delay caused.

14. The Firm executing the work should arrange while handing over the installation to this Department to pass a certificate of guarantee for the continuance of satisfactory service to the installation for a period of 12 calendar months from the date of handing over charge to this Department, while uninterrupted power supply is maintained. Further, it will be obligatory on the part of the firm to attend to any defects in the installation that might crop up during the above period without any return for service rendered.

15. *Details of work.*—The quantities given in the annexed statement are not guranteed and are subject to variation at the time of executing the work.

N.B.—Large metal junction boxes should be employed for wiring outlets.

Installing Electric lights to the Maternity Hospital Building at Krishnarajanagar.

No.	Names of materials	Unit	Quantity
	Part I—Mains, Sub-mains and Distribution board, etc.		
1	Supplying, fixing and tarring S. M. Rail 24 feet long	No.	1
2	Do 2-pin S. C. A. complete with clamps, etc.	Set	2
3	Do shackle insulators with straps, etc., complete ..	No.	4
4	Do guy set complete with anchor rod, 7 strand guy-wire and 6 feet long 2″ galvanized guard pipe	Set	1
5	Supplying and stringing copper wire No. 8 B. & S. (Bare)	Lbs.	8
6	Supplying and running mains ¾″ W. I. pipe embedded in wall with bends, etc., using No. 7/.044 SWG. insulated wire and accessories ..	Ft.	35
7	Supplying and running sub-mains in ¾″ W. I. pipe embedded in wall using No. 7/.036 SWG. insulated wire and accessories	Ft.	15
8	Do No. 7/.036 SWG. twin conductor paper insulated, lead covered double steel tape armoured jute served underground cable laid in a trench of 3′ deep surrounded by 3″ fine sand enclosing the ends in Indoor type junction boxes, filled with insulating compound using necessary accessories, etc.	Ft.	55
9	Supplying, fixing and wiring T. W. board 30″×20″×1″ with 2″ battens and ½″ rear board equipping it with 2 D. P. S. T. 15 Amps. ironclad switches with fuses using No. 7/.036 SWG. insulated wire and accessories ..	No.	1
10	Do sub-distribution board 15″×12″×1″ with batten and rear board equipped with a 15 amp. D. P. S. T. ironclad switch with fuses using No. 7/.036 SWG. insulated wire and accessories as above	,,	1
11	Earthing	L. S.	..

No.	Names of Materials	Unit	Quantity
	Part II—Interior Wiring.		
1	Supplying, fixing and wiring in twin and tripple conductor, lead covered cables run on T. W. fillets embedded in the wall for lighting outlets complete with necessary junction boxes 5 Amps., S. P. Control switches with reinforced cream bakelite cover using No. 7/.029 and 3/.036 SWG. L. C. cables for mains and taps respectively and accessories— Hospital .. .. 11 Ward .. .. 10 ..	No.	21
2	Do for wall plug outlets complete with 5 Amps. 2-pin combined wall plug and switch with nipple as per specification above— Hospital .. .. 1 Ward 2	,,	3
3	Supplying, fixing and wiring 'Hailware' ceiling fittings Cat. No. H. 7 complete with B. C. lamp holder 9" opal glassware, etc., using necessary accessories— Hospital .. .. 3 Ward .. .. 4 ..	,,	7
4	Do adjustable pendent complete with counterweight, ring pulley 2 plate bakelite ceiling rose, lead shots flexible cord B. C. Lamp holder 10"×5" tin enamelled shade, etc., using necessary accessories— Ward	,,	1
5	Do for drop lights complete with bakelite 2-plate ceiling rose, flexible cord B. C. lamp holder 10"×5" green and white opal shades and accessories— Hospital .. .. 5 Ward .. .. 1 ..	,,	6
6	Do 6"×½" O. C. brackets complete with O. C. B. C. Lamp-holder 10"×5" green and white opal shade, etc., as above— Hospital .. .. 3 Ward .. .. 4 ..	,,	7
7	Supplying and fixing lamps, 60 watts, B. C. 230 volts, gas filled frosted 'Mysore'— Hospital .. .. 8 Ward .. .. 5 ..	,,	13
8	Do 100 watt as above 'Mysore'— Hospital .. .. 3 Ward .. .. 4 ..	,,	7
9	Do 150 watts as above 'Mysore'— Ward	,,	1
10	Earthing	L. S.	..
	Part III—Heating.		
1	Supplying, fixing and wiring on the board available one D. P. S. T. 15 Amps. ironclad switch with fuses using No. 7/.044 SWG. insulated wire and accessories	No.	1
2	Supplying, fixing and wiring in twin conductor No. 7/.036 L. C. Cable run on T. W. fillet one 15 Amp. combined wall plug and switch with nipple protected by a pair of fuses 15 Amps. Home Office type using necessary accessories	,,	1
3	Earthing	L. S.	..

M. M. ALI KHAN,
Superintendent.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, BHADRAVATI.

Abstract Notification No. 10028, *dated* 15—17*th June* 1940.

The attention of the public is invited to the detailed notification calling for sealed tenders for the work of 'Installing Electric Lights to the Civil Hospital at Chitaldrug' published on pages 1456-1460, Part VI of the *Mysore Gazette*, dated 13th June 1940. The last date of receiving tenders is 11 A.M., 6th July 1940. Earnest money required is Rs. 135.

K. SUBBA RAO,
Superintendent.